



IT IS ASSUMED THAT ALL WORKS ON THIS DRAWING WILL BE CARRIED OUT BY A COMPETENT CONTRACTOR WORKING, WHERE APPROPRIATE, TO AN APPROPRIATE METHOD STATEMENT.

THIS DRAWING IS TO BE USED ONLY FOR THE PURPOSE OF ISSUE THAT IT WAS ISSUED FOR.

- NOTES:
- ALL DIMENSIONS ARE IN METRES UNLESS OTHERWISE STATED.
  - THE INFORMATION ON THIS PLAN IS GIVEN WITHOUT OBLIGATION OR WARRANTY. NO LIABILITY OF ANY KIND WHATSOEVER IS ACCEPTED BY AECOM FOR ANY ERRORS OR OMISSIONS.
  - DRAWING IS BASED ON ORDNANCE SURVEY MAPPING AND TOPOGRAPHICAL SURVEY SUPPLIED BY PLOWMAN CRAVEN (DATED MAY 2020).
  - ITEMS IN GREY (APART FROM SOLID HATCHING) REPRESENT EXISTING INFRASTRUCTURE AND ARE TO REMAIN UNLESS STATED OTHERWISE.
  - NEW FOOTWAY AND CARRIAGEWAY INSPECTION CHAMBER COVERS LINKED TO STATUTORY UNDERTAKERS APPARATUS ARE NOT SHOWN ON THIS DRAWING REVISION.
  - CURRENT TOPOGRAPHICAL SURVEY DOES NOT COVER THE EXTENTS OF THE PROPOSED APPLEFORD SHUTTLE ARRANGEMENT. THIS SECTION IS BASED ON THE ORDNANCE SURVEY MAPPING AND AERIAL PHOTOGRAPHY. EXISTING LIGHTING EQUIPMENT HAS BEEN SHOWN ON THIS DRAWING WITHIN THE SCHEME EXTENTS ONLY.



REVISION DETAILS	By	Check	Date	Suffix
FIRST ISSUE	AC	JL	19/08/21	P01
SECOND ISSUE	AZ	AGB	16/06/22	P02

SUITABLE FOR INFORMATION

Client  
**OXFORDSHIRE COUNTY COUNCIL**

Project Title  
**DIDCOT GARDEN TOWN HOUSING INFRASTRUCTURE FUND (HIF 1)**

Drawing Title  
**A4130 WIDENING SCHEME WIDE LIGHTING LAYOUT SHEET 3 OF 19**

Designed AZ	Drawn AZ	Checked KC	Approved AGB	Date 27/06/23
Internal Project No. 60632497	Suitability S2	Discipline Town & Country Planner		

THIS DOCUMENT HAS BEEN PREPARED PURSUANT TO AND SUBJECT TO THE TERMS OF AECOM'S APPOINTMENT BY ITS CLIENT. AECOM ACCEPTS NO LIABILITY FOR ANY USE OF THIS DOCUMENT OTHER THAN BY ITS ORIGINAL CLIENT OR FOLLOWING AECOM'S EXPRESS AGREEMENT TO SUCH USE, AND ONLY FOR THE PURPOSES FOR WHICH IT WAS PREPARED AND PROVIDED.

AECOM  
63-77 Victoria Street  
St Albans  
Herts  
AL1 3ER  
Tel: +44 (0) 172 7535 000  
www.aecom.com

**AECOM**  
AECOM Infrastructure & Environment UK Limited  
Registered in England Registered number: 880328  
Registered office: Midpoint, Alconon Link,  
Basingstoke, Hampshire RG21 7PP

Work Package ID	Volume	Type	Number	Rev
GEN_PD-ACM-HLG-DGT_LTG_ZZ-DR-T-1303				P03

© Crown Copyright [and database rights Oxfordshire County Council] [2022] OS [0100023343]. You are permitted to use this data solely to enable you to respond to, or interact with, the organisation that provided you with the data. You are not permitted to copy, sub-licence, distribute or sell any of this data to third parties in any form.

**LEGEND**

**A** Supply and install new DW Windsor Kirium Pro 2 luminaire side entry mounted on new 10m Valmont Stainton Avon conical tapered steel lighting column (to OCC specification, see HSD 1300-021). Transfer all attachments from adjacent removed lighting column (if applicable). Terminate cables in new isolator in base of column.  
MOUNTING: 0.75m with 5° uplift side entry bracket, lantern to be installed at -5°  
LED OUTPUT: CLO, 500mA, 82W, 11.34klm  
OPTIC: 64LED 3k A5  
DIMMING: 100%, 75% 00:00 to 06:00  
SWITCHING: 7-pin NEMA socket with Westire 7200 series 35/18 Photocell

**B** Supply and install new DW Windsor Kirium Pro 2 luminaire side entry mounted on new 5m Abacus Raise & Lowering spring operated column (to OCC specification, see HSD 1300-007). Terminate cables in new isolator in base of column.  
MOUNTING: 0.75m with 5° uplift side entry bracket, lantern to be installed at -5°  
LED OUTPUT: CLO, 750mA, 125W, 15.88klm  
OPTIC: 64LED 3k A5  
DIMMING: 100%, 75% 00:00 to 06:00  
SWITCHING: 7-pin NEMA socket with Westire 7200 series 35/18 Photocell

**C** Supply and install new DW Windsor Kirium Pro Mini luminaire post top mounted on new 5m Abacus Raise & Lowering spring operated column (to OCC specification, see HSD 1300-007). Terminate cables in new isolator in base of column.  
MOUNTING: Post top, 0° tilt  
LED OUTPUT: CLO, 600mA, 27W, 3.83klm  
OPTIC: 16LED 3k A2  
DIMMING: 100%, 75% 00:00 to 06:00  
SWITCHING: 7-pin NEMA socket with Westire 7200 series 35/18 Photocell

**00** Proposed Column/Sign Identifier  
**DNO-N** Proposed Electrical Supply Type  
SUPPLY TYPE  
DNO: Distributor Network Operator  
PCN: Private Connection Network  
DNO-[N] / [D] / [T] / [R]: DNO new service / disconnection / transfer / remain.  
PCN-[N] / [D] / [T] / [R]: PCN new service / disconnection / transfer / remain.

File Name: C:\P\WORKING\AECOM\0302\_UK-CL-TSH\AVIAN\GURUKA@AECOM\CON\01130623\GEN\_PD-ACM-HLG-DGT\_LTG\_ZZ-DR-T-1303  
 Rev: 1.0  
 Date: 27/06/23