


IT IS ASSUMED THAT ALL WORKS ON THIS DRAWING WILL BE CARRIED OUT BY A COMPETENT CONTRACTOR WORKING, WHERE APPROPRIATE, TO AN APPROPRIATE METHOD STATEMENT.

THIS DRAWING IS TO BE USED ONLY FOR THE PURPOSE OF ISSUE THAT IT WAS ISSUED FOR.

- NOTES:
1. ALL DIMENSIONS ARE IN METRES UNLESS OTHERWISE STATED.
 2. THE INFORMATION ON THIS PLAN IS GIVEN WITHOUT OBLIGATION OR WARRANTY. NO LIABILITY OF ANY KIND WHATSOEVER IS ACCEPTED BY AECOM FOR ANY ERRORS OR OMISSIONS.
 3. DRAWING IS BASED ON ORDNANCE SURVEY MAPPING AND TOPOGRAPHICAL SURVEY SUPPLIED BY PLOWMAN CRAVEN (DATED MAY 2020).
 4. ITEMS IN GREY (APART FROM SOLID HATCHING) REPRESENT EXISTING INFRASTRUCTURE AND ARE TO REMAIN UNLESS STATED OTHERWISE.
 5. NEW FOOTWAY AND CARRIAGEWAY INSPECTION CHAMBER COVERS LINKED TO STATUTORY UNDERTAKERS APPARATUS ARE NOT SHOWN ON THIS DRAWING REVISION.
 6. CURRENT TOPOGRAPHICAL SURVEY DOES NOT COVER THE EXTENTS OF THE PROPOSED APPLEFORD SHUTTLE ARRANGEMENT. THIS SECTION IS BASED ON THE ORDNANCE SURVEY MAPPING AND AERIAL PHOTOGRAPHY.
 7. EXISTING LIGHTING EQUIPMENT HAS BEEN SHOWN ON THIS DRAWING WITHIN THE SCHEME EXTENTS ONLY.



FIRST ISSUE	AC	JL	19/08/21	P01
SECOND ISSUE	AZ	AGB	16/06/22	P02
THIRD ISSUE	SK	JL	18/04/23	P03
FOURTH VERSION	SK	AGB	23/04/23	P04
REVISION DETAILS		By	Date	Suffix
Purpose of issue		Check		

SUITABLE FOR APPROVAL

Client
OXFORDSHIRE COUNTY COUNCIL

Project Title
DIDCOT GARDEN TOWN HOUSING INFRASTRUCTURE FUND (HIF 1)

Drawing Title
CLIFTON HAMPDEN BYPASS SCHEME WIDE LIGHTING LAYOUT SHEET 16 OF 19

Designed SK	Drawn SK	Checked JL	Approved AGB	Date 27/06/23
Internal Project No. 60632497	Suitability S4	Scale @ A1 1:1000		
Discipline Town & Country Planner		THIS DOCUMENT HAS BEEN PREPARED PURSUANT TO AND SUBJECT TO THE TERMS OF AECOM'S APPOINTMENT BY ITS CLIENT. AECOM ACCEPTS NO LIABILITY FOR ANY USE OF THIS DOCUMENT OTHER THAN BY ITS ORIGINAL CLIENT OR FOLLOWING AECOM'S EXPRESS AGREEMENT TO SUCH USE, AND ONLY FOR THE PURPOSES FOR WHICH IT WAS PREPARED AND PROVIDED.		

AECOM
63-77 Victoria Street
St Albans
Herts
AL1 3ER
Tel: +44 (0) 1272 7535 000
www.aecom.com

AECOM
AECOM Infrastructure & Environment UK Limited
Registered in England Registered number: 880328
Registered office: Midpoint, Alconon Link,
Basingstoke, Hampshire RG21 7PP

Drawing Number	Volume	Type	Number	Rev
GEN_PD-ACM-HLG-DGT_LTG_ZZ-DR-T-1316				P05
Originator	Location	Role		

© Crown Copyright [and database rights Oxfordshire County Council] [2022] OS [0100023343]. You are permitted to use this data solely to enable you to respond to, or interact with, the organisation that provided you with the data. You are not permitted to copy, sub-licence, distribute or sell any of this data to third parties in any form.

KEY

- A** Supply and install new DW Windsor Kirium Pro 2 luminaire side entry mounted on new 10m Valmont Stainton Avon conical tapered steel lighting column (to OCC specification, see HSD 1300-021). Transfer all attachments from adjacent removed lighting column (if applicable). Terminate cables in new isolator in base of column.
MOUNTING: 0.75m with 5° uplift side entry bracket, lantern to be installed at -5°
LED OUTPUT: CLO, 650mA, 82W, 11.61km
OPTIC: 48LED 3k D1
DIMMING: 100%, 75% 00:00 to 6:00
SWITCHING: 7-pin NEMA socket with Westire 7200 series 35/18 Photocell
- D** Supply and install new DW Windsor Kirium Pro Mini luminaire side entry mounted on new 6m Valmont Stainton Avon conical tapered steel lighting column (to OCC specification, see HSD 1300-021). Transfer all attachments from adjacent removed lighting column (if applicable). Terminate cables in new isolator in base of column.
MOUNTING: Post Top Mounted CLO, 500mA, 23W, 3.27km
LED OUTPUT: 16LED 3k D3
OPTIC: 100%, 75% 00:00 to 06:00
DIMMING: 100%, 75% 00:00 to 06:00
SWITCHING: 7-pin NEMA socket with Westire 7200 series 35/18 Photocell
- E** Supply and install new DW Windsor Kirium Pro 2 luminaire side entry mounted on new 8m Valmont Stainton Avon conical tapered steel lighting column (to OCC specification, see HSD 1300-021). Transfer all attachments from adjacent removed lighting column (if applicable). Terminate cables in new isolator in base of column.
MOUNTING: 0.75m with 5° uplift side entry bracket, lantern to be installed at -5°
LED OUTPUT: CLO, 600mA, 52W, 6.99km
OPTIC: 32LED 3k D1
DIMMING: 100%, 75% 00:00 to 06:00
SWITCHING: 7-pin NEMA socket with Westire 7200 series 35/18 Photocell
- F** Supply and install new DW Windsor Kirium Pro Mini luminaire side entry mounted on new 5m Abacus Raise & Lowering spring operated column (to OCC specification, see HSD 1300-007). Terminate cables in new isolator in base of. Transfer all attachments from adjacent removed lighting column (if applicable). Terminate cables in new isolator in base of column.
MOUNTING: Post Top Mounted CLO, 750mA, 19W, 2.28km
LED OUTPUT: 8LED 3k D1
OPTIC: 84LED 3k A5
DIMMING: 100%, 75% 00:00 to 06:00
SWITCHING: 7-pin NEMA socket with Westire 7200 series 35/18 Photocell
- G** Supply and install new DW Windsor Kirium Pro 2 luminaire side entry mounted on new 10m Valmont Stainton Avon conical tapered steel lighting column (to OCC specification, see HSD 1300-021). Transfer all attachments from adjacent removed lighting column (if applicable). Terminate cables in new isolator in base of column.
MOUNTING: 0.75m with 5° uplift side entry bracket, lantern to be installed at -5°
LED OUTPUT: CLO, 550mA, 91W, 12.31km
OPTIC: 64LED 3k A5
DIMMING: 100%, 75% 00:00 to 06:00
SWITCHING: 7-pin NEMA socket with Westire 7200 series 35/18 Photocell
- H** Supply and install new DW Windsor Kirium Pro Mini luminaire post top mounted on new 5m Abacus Raise & Lowering spring counterbalance column (to OCC specification, see HSD 1300-007). Transfer all attachments from adjacent Removed lighting column (if applicable). Terminate cables in new isolator in base of column.
MOUNTING: Post Top Mounted CLO, 850mA, 39W, 4.83km
LED OUTPUT: 16LED 3k A2
OPTIC: 100%, 75% 00:00 to 06:00
DIMMING: 100%, 75% 00:00 to 06:00
SWITCHING: 7-pin NEMA socket with Westire 7200 series 35/18 Photocell
- DNO-R** Proposed Column/Sign Identifier Proposed Electrical Supply Type